



Al Hadeeqa Contracting Co. L.L.C

شركة الحديقة للمقاولات ش.ذ.م.م

UNDERGROUND BUNKER SOLUTIONS — COMPLETE PRODUCT GUIDE

Six tiers designed to match every budget, property type and protection need

Al Hadeeqa Contracting Co. L.L.C — Dubai, U.A.E — March 2026

EMERGENCY POD

AED 100K

COMPACT SHELTER

AED 200K

SHELTER

From 500K

SAFE ROOM

From 950K

FORTIFIED RESIDENCE

From 1.9M

THE VAULT

From 5M+

COMPLETE PRODUCT MAP

SPECIFICATION	POD	COMPACT	SHELTER	SAFE ROOM	FORTIFIED	VAULT
Type	Precast	Precast	Poured	Poured	Poured	Poured
Size	7-8 sqm	15-20 sqm	25-35 sqm	50-80 sqm	100-150 sqm	300-500+
Capacity	2-4	6-8	8-15	10-20	15-25	15-30
Depth	2.5-3m	3-3.5m	3-4m	4-5m	5-6m	5-6m
Autonomy	12-24h	1-3 days	1-3 days	3-7 days	7-14 days	14+ days
Entry	Top hatch	Top hatch	Ladder	Staircase	Wide stair	Car ramp
Walls	220mm	250mm	300-400mm	400mm	400-500mm	500mm
Ventilation	Manual	Manual+fan	HEPA	2x HEPA	Redundant	Redundant+
Power	Lanterns	Batt 24h	Batt 48h	Batt72h+gen	7d+gen	14d+gen
Bedrooms	0	0	0	1-2	2-3	2-3+
Bathroom	Chem.	Chem.	1 basic	1-2	2-3 en-suite	2-3 en-s.
Price From	AED 100K	AED 200K	AED 500K	AED 950K	AED 1.9M	AED 5M+

- Precast tiers (Pod, Compact): factory-made in Al Hadeeqa's Ajman yard, delivered by truck, dropped into excavated pit.
- Poured tiers (Shelter and above): built on-site with traditional formwork.
- Custom sizes at AED 15,200/sqm.



Al Hadeeqa Contracting Co. L.L.C

شركة الحديقة للمقاولات ش.ذ.م.م

EMERGENCY POD

Precast Drop-In | 7–8 sqm | 2–4 People

STARTING FROM
AED 100,000

The absolute entry-level product. A single precast reinforced concrete box manufactured in Al Hadeeqa's Ajman yard, trucked to the client's property and lowered into a pre-dug pit by crane. For couples, small families, or as a secondary shelter for staff quarters.

DIMENSIONS & STRUCTURE

Internal:	2.5m W × 3.0m D × 2.0m H (7.5 sqm)
External:	2.94m × 3.44m × 2.25m
Weight:	8–10 tonnes (crane required)
Walls:	220mm reinforced concrete, C40
Roof:	250mm reinforced concrete
Floor:	220mm RC (integral to unit)
Rebar:	Double-layer mesh, 12–16mm bars
Waterproof:	Crystalline admixture + bitumen paint
Depth:	2.5–3.0m below grade

INSTALLATION SCOPE

- Excavation: ~3.5m × 4.0m × 3.0m deep
- Base: 100mm gravel + 75mm lean concrete
- Crane lowers unit into pit (1–2 hours)
- Backfill + surface restoration
- Hatch at grade, concealed with paver lid
- Manufacturing: 5–7 days in Ajman yard
- Site works: 1–2 days after unit delivery

WHAT'S INCLUDED

ENTRY & ACCESS

- ✓ Steel top-entry hatch (lockable, weather-sealed)
- ✓ Fixed steel ladder (4–5 rungs)
- ✗ Blast door — not included (cost saving)
- ✗ Staircase

VENTILATION

- ✓ 1× manual hand-crank fan (no power needed)
- ✓ Fresh air intake pipe (50mm PVC + rain cap)
- ✓ Exhaust vent pipe (50mm, opposite wall)
- ✗ HEPA filtration — optional upgrade

POWER

- ✗ No electrical system installed
- ✓ 2× battery-powered LED lanterns
- ✓ 1× rechargeable USB power bank

WATER & SANITATION

- ✓ 2× 20L water jerry cans (40L total)
- ✓ 1× portable chemical toilet + chemicals
- ✗ No plumbing or drainage

SAFETY & COMMS

- ✓ 2× fold-down bench/sleep surfaces
- ✓ Storage shelf + first aid kit + fire extinguisher
- ✓ 1× walkie-talkie set (surface + inside)
- ✗ No intercom, no satellite

OPTIONAL UPGRADES (priced separately)

HEPA filtration • 12V battery + LED lighting • Blast-rated hatch • Hardwired intercom • 500L water tank
AED 100,000 — Free site assessment available. Contact Al Hadeeqa.



Al Hadeeqa Contracting Co. L.L.C

شركة الحديقة للمقاولات ش.ذ.م.م

COMPACT SHELTER

Precast Drop-In | 15–20 sqm | 6–8 People

STARTING FROM
AED 200,000

A meaningful step up from the Pod. Still precast and factory-made, but large enough for a family of 6–8 to shelter for 1–3 days with real facilities: HEPA filtration, battery power, intercom and a proper water tank. Constructed as two interlocking precast halves, bolted and grouted on site.

DIMENSIONS & STRUCTURE

Internal:	4.0m W × 4.5m D × 2.2m H (18 sqm)
External:	4.5m × 5.0m × 2.5m
Weight:	18–22 tonnes (crane required)
Walls:	250mm reinforced concrete, C40
Roof:	250mm reinforced concrete
Rebar:	Double-layer 16mm bars, 150mm c/c
Waterproof:	Crystalline + bitumen + drainage layer
Joint:	Interlocking halves, grouted + bolted
Depth:	3.0–3.5m below grade

INSTALLATION SCOPE

- Excavation: ~5.0m × 5.5m × 3.5m deep
- Base: 150mm gravel + 100mm lean concrete
- Crane places 2 halves, bolted + grouted
- Backfill + surface restoration
- MEP: vents, battery system, intercom wired
- Manufacturing: 10–14 days in Ajman yard
- Site works: 2–3 days after delivery

WHAT'S INCLUDED

ENTRY & ACCESS

- ✓ Steel top-entry hatch (rubber gasket sealed)
- ✓ Fixed steel ladder with handrails (6–7 rungs)
- ✗ Blast door — not included

VENTILATION

- ✓ 1× HEPA filtration unit (single-stage)
- ✓ 1× 12V electric inline fan
- ✓ 1× manual hand-crank fan (backup)
- ✓ 75mm intake + exhaust pipes with filter screens

POWER

- ✓ 2× 100Ah deep-cycle battery bank (12V)
- ✓ LED strip lighting throughout (~6 fixtures)
- ✓ 2× USB charging outlets + battery monitor
- ✗ No generator hookup, no 240V AC

WATER & SANITATION

- ✓ 200L water tank with gravity-fed tap
- ✓ Portable chemical toilet + privacy curtain
- ✓ Hand-wash basin (gravity-fed, 20L drain container)
- ✗ No hot water, shower or mains plumbing

SAFETY & COMMS

- ✓ 4× fold-down bunks (sleep 4–6)
- ✓ Fold-down table + 2× storage shelves
- ✓ 1× CO2 / air quality alarm
- ✓ 1× hardwired intercom to surface
- ✓ 1× battery radio (AM/FM emergency)
- ✗ No satellite phone

OPTIONAL UPGRADES (priced separately)

Blast-rated hatch • Solar panel + charge controller • Satellite phone • Portable gas cooktop • 500L water tank

AED 200,000 — Free site assessment available. Contact Al Hadeeqa.

Tel.: +971 4 263 2371
Fax: +971 4 263 3276
P.O.Box: 234305
Dubai - U.A.E

Mobile: +971 544419854
+971 504824621
E-mail: alhadeeqallc@gmail.com

تليفون : +971 4 263 2371
ت / فاكس : +971 4 263 3276
ص.ب : ٢٣٤٣٠٥
دبي - أ.ع.م



Al Hadeeqa Contracting Co. L.L.C

شركة الحديقة للمقاولات ش.ذ.م.م

SHELTER

Poured-in-Place | 7.0m × 4.0m | 28 sqm | 8–15 People

STARTING FROM

From AED 500,000

The entry point for traditional poured-in-place bunkers. Custom-built on the client's property with full formwork, thicker walls and proper MEP systems. Significant jump in protection vs precast. Features a certified blast door, full bathroom, 500L water storage and 48-hour battery.

DIMENSIONS & STRUCTURE

Internal:	7.0m W × 4.0m D × 3.0m H (28 sqm)
Depth:	3.0–4.0m below grade
Walls:	300–400mm RC, C40, double-layer 16–20mm
Roof:	400–450mm reinforced concrete
Base:	400–450mm reinforced concrete
Waterproof:	Membrane + crystalline + PVC waterstops
Layout:	Open room + bathroom + entry corridor
Construction:	Poured-in-place, full formwork on-site

INSTALLATION SCOPE

- Full excavation on client property
- Formwork erected + steel rebar fixed
- Concrete poured in stages (walls, roof, base)
- Full MEP: power, water, drainage installed
- Blast door + airtight door fitted
- Internal finishes + fixtures installed
- Timeline: 4–6 weeks site works total
- Custom sizes: AED 15,200/sqm

WHAT'S INCLUDED

ENTRY & ACCESS

- ✓ Blast-resistant steel door (certified)
- ✓ Air-tight secondary door (rubber gasket)
- ✓ Steel ladder with safety cage from surface
- ✓ Emergency escape hatch (roof-mounted)
- ✗ No staircase — ladder only

VENTILATION

- ✓ 1× HEPA air filtration unit
- ✓ 1× electric ventilation fan
- ✓ 1× manual hand-crank backup fan
- ✓ Blast-protected surface caps + ductwork

POWER

- ✓ Battery bank: 48hr runtime
- ✓ LED panel lighting (~10 fixtures)
- ✓ Switch panel + 4–6 socket outlets
- ✓ Distribution board with RCD + earthing
- ✗ No generator hookup

WATER & SANITATION

- ✓ 500L water storage tank
- ✓ Full bathroom: toilet + sink + shower
- ✓ Cold water supply + drainage pipes
- ✓ Sewage holding tank + submersible pump
- ✓ Water heater (instant electric) + kitchenette

FINISHES & COMMS

- ✓ Polished concrete floors
- ✓ Painted walls + ceramic tile in bathroom
- ✓ Hardwired intercom + CO2 detector
- ✓ 2× fire extinguishers + first aid kit
- ✗ No satellite phone (optional upgrade)

OPTIONAL UPGRADES (priced separately)

Satellite phone • Mobile repeater • Generator hookup • Solar panels • Tiled floors • Custom fitout

From AED 500,000 — Free site assessment available. Contact Al Hadeeqa.

Tel.: +971 4 263 2371
Fax: +971 4 263 3276
P.O.Box: 234305
Dubai - U.A.E

Mobile: +971 544419854
+971 504824621
E-mail: alhadeeqallc@gmail.com

تليفون : +971٤٢٦٣٢٣٧١
ت / فاكس : +971٤٢٦٣٣٢٧٦
ص.ب : ٢٣٤٣٠٥
دبي - أ.ع.م



Al Hadeeqa Contracting Co. L.L.C

شركة الحديقة للمقاولات ش.ذ.م.م

SAFE ROOM

Poured-in-Place | 50–80 sqm | 10–20 People | 3–7 Day Autonomy

STARTING FROM

From AED 950,000

The core product. Everything in the Shelter plus separate bedrooms, full kitchen, dual HEPA redundancy, generator hookup and satellite comms. Comfortable for days to a week. Includes the existing 138 sqm design at the upper end of the range.

DIMENSIONS & STRUCTURE

Internal:	50–80 sqm (e.g. 10m × 6m or 8m × 8m)
Depth:	4.0–5.0m below grade
Walls:	400mm RC, C40/C50, double-layer 20mm rebar
Roof:	450–500mm reinforced concrete
Base:	450mm reinforced concrete
Waterproof:	Full spec: membrane + crystalline + waterstops
Layout:	Hall + 1–2 bedrooms + 2 + kitchen bathrooms
Entry:	Staircase descent + emergency ladder
Construction:	Poured-in-place, staged casting

INSTALLATION SCOPE

- Full excavation on client property
- Formwork + rebar for staircase and all walls
- All MEP: power, water, drainage, comms
- Blast + airtight doors fitted
- Generator hookup provision at surface
- Full internal fitout + finishes
- Timeline: 6–8 weeks site works total
- Custom sizes: AED 15,200/sqm

WHAT'S INCLUDED

ENTRY & ACCESS

- ✓ Blast-resistant + airtight double-door entry
- ✓ Proper staircase descent (not just ladder)
- ✓ Emergency ladder + escape hatch

VENTILATION

- ✓ 2× HEPA units (dual redundancy)
- ✓ Electric fans on both units + manual backup
- ✓ Blast-protected surface caps, full ductwork

POWER

- ✓ Battery bank: 72hr+ runtime
- ✓ Generator hookup provision at surface
- ✓ Full LED lighting + recessed fixtures
- ✓ Multiple socket outlets throughout

WATER & SANITATION

- ✓ 1,000L water storage + basic filtration
- ✓ 1–2 full bathrooms (tiled, proper fixtures)
- ✓ Full kitchen with countertops + cooktop
- ✓ Sewage holding tank + submersible pump

FINISHES & COMMS

- ✓ Engineered wood / luxury vinyl flooring
- ✓ Ceramic tile in bathrooms + kitchen
- ✓ Recessed LED lighting with dimming
- ✓ Built-in cabinetry throughout
- ✓ Satellite phone + mobile signal repeater
- ✓ Pre-wired for TV + entertainment

OPTIONAL UPGRADES (priced separately)

Generator upgrade • 2,000L water • Smart lighting • CCTV • Custom fitout • Pool table / entertainment

From AED 950,000 — Free site assessment available. Contact Al Hadeeqa.

Tel.: +971 4 263 2371
Fax: +971 4 263 3276
P.O.Box: 234305
Dubai - U.A.E

Mobile: +971 544419854
+971 504824621
E-mail: alhadeeqallc@gmail.com

تليفون : +٩٧١٤٢٦٣٢٣٧١
ت/ فاكس : +٩٧١٤٢٦٣٣٢٧٦
ص.ب : ٢٣٤٣٠٥
دبي - أ.ع.م



Al Hadeeqa Contracting Co. L.L.C

شركة الحديقة للمقاولات ش.ذ.م.م

FORTIFIED RESIDENCE

Poured-in-Place | 100–150 sqm | 15–25 People | 7–14 Day Autonomy

STARTING FROM

From AED 1,900,000

The pinnacle of the Al Hadeeqa bunker line. Everything in the Safe Room plus a master suite with en-suite, full entertainment, 7–14 day autonomy, premium finishes and smart home systems. Built as an underground home that happens to be blast-proof.

DIMENSIONS & STRUCTURE

Internal:	100–150 sqm (e.g. 15m × 8m or × 12m 10m)
Depth:	5.0–6.0m below grade
Walls:	400–500mm RC, C50, triple-layer rebar
Roof:	500mm+ reinforced concrete
Base:	500mm reinforced concrete
Waterproof:	Premium: multi-layer membrane + drainage board
Layout:	Master suite + 1–2 beds + room entertainment
Entry:	Wide staircase (1.2m+) + ladder emergency
Construction:	Poured-in-place, full design-and-build

INSTALLATION SCOPE

- Full excavation — larger footprint, deeper dig
- Staged concrete pours with full shoring
- Complete MEP design + installation
- Climate control (split AC, generator-backed)
- Smart home systems installation
- Premium fitout + custom millwork
- Timeline: 10–14 weeks total
- Custom sizes: AED 15,200/sqm

WHAT'S INCLUDED

ENTRY & ACCESS

- ✓ Double blast-rated entry with decon corridor
- ✓ Wide staircase 1.2m+ with balustrade
- ✓ Emergency escape hatch + ladder

SYSTEMS

- ✓ Redundant HEPA + activated carbon filtration
- ✓ CO2 monitoring + auto fresh-air cycling
- ✓ Dual battery bank: 7+ day runtime
- ✓ Diesel generator with auto-transfer switch
- ✓ 2,000L+ water + multi-stage filtration
- ✓ Full satellite + CCTV of all access points
- ✓ Climate control: split AC, generator-backed

FINISHES

- ✓ Natural stone / premium large-format tile
- ✓ Designer bathroom fixtures (Grohe / Duravit)
- ✓ Custom millwork throughout
- ✓ Smart home lighting (scene control)
- ✓ Acoustic treatment in entertainment area
- ✓ Solid-core premium doors throughout

ENTERTAINMENT

- ✓ Pool table (tournament 9ft)
- ✓ 85–100" screen + surround sound
- ✓ Gaming console setup + bar with seating
- ✓ Beverage fridge + wine storage

OPTIONAL UPGRADES (priced separately)

Extended generator runtime • Additional bedrooms • Home cinema upgrade • Custom millwork • Smart automation • Panic room within
From AED 1,900,000 — Free site assessment available. Contact Al Hadeeqa.

Tel.: +971 4 263 2371
Fax: +971 4 263 3276
P.O.Box: 234305
Dubai - U.A.E

Mobile: +971 544419854
+971 504824621
E-mail: alhadeeqallc@gmail.com

تليفون : +971 4 263 2371
ت / فاكس : +971 4 263 3276
ص.ب : ٢٣٤٣٠٥
دبي - أ.ع.م



Al Hadeeqa Contracting Co. L.L.C

شركة الحديقة للمقاولات ش.ذ.م.م

THE VAULT

Poured-in-Place | 300–500+ sqm | Underground Luxury Living | Separate Product

STARTING FROM

AED 5,000,000+

The Vault is a separate product category — not just a large bunker but a complete underground home built to bunker-grade structural standards. Car ramp entry, underground garage, cinema, gym, lounge and bar, multiple bedrooms, full luxury living. Marketed separately with dedicated branding and a standalone concept brief available on request.

DIMENSIONS & SCOPE

Internal:	300–500+ sqm (fully custom)
Depth:	5.0–6.0m below grade
Walls:	500mm+ RC, C50, premium specification
Roof:	500mm+ reinforced concrete
Entry:	Car ramp + blast-rated vehicle gate
Layout:	Garage + living + cinema + gym + bar
Construction:	Full design-and-build, 16–26 weeks
Waterproof:	Premium multi-layer system

WHAT'S INCLUDED

- Underground garage (2–4 cars)
- Full residential kitchen + dining area
- Home cinema: 4K projector + premium seating
- Gym + wellness area
- Lounge + bar + wine cellar
- Master suite + 2–3 additional bedrooms
- En-suite bathrooms to all bedrooms
- 14-day+ autonomy with diesel generator
- 2,000L+ water + full filtration system
- Full CCTV + access control + smart home

SYSTEMS & PROTECTION

PROTECTION SYSTEMS

- ✓ Redundant HEPA + activated carbon filtration
- ✓ CO2 monitoring + auto air cycling
- ✓ Dual diesel generators with auto-transfer
- ✓ 14-day battery bank backup
- ✓ Full satellite phone + comms
- ✓ CCTV: garage + entry + surface perimeter
- ✓ Climate control: multi-zone AC
- ✓ Blast-rated vehicle gate + pedestrian door

FINISHES & ENTERTAINMENT

- ✓ Natural stone or large-format marble tile
- ✓ Custom millwork and cabinetry throughout
- ✓ Designer bathroom: Grohe / Duravit / Villeroy
- ✓ Smart home: Crestron / Control4 level
- ✓ Acoustic cinema room with 4K projection
- ✓ Tournament pool table (9ft)
- ✓ Custom bar + wine fridge + cellar

THE VAULT IS A SEPARATE PRODUCT — CONTACT AL HADEEQA FOR THE FULL CONCEPT BRIEF

Custom design • Dedicated project team • Starting from AED 5,000,000

Tel: +971 4 263 2371 | Mobile: +971 544419854 | alhadeeqallc@gmail.com

Tel.: +971 4 263 2371
Fax: +971 4 263 3276
P.O.Box: 234305
Dubai - U.A.E

Mobile: +971 544419854
+971 504824621
E-mail: alhadeeqallc@gmail.com

تليفون : +971 4 263 2371
ت / فاكس : +971 4 263 3276
ص.ب : ٢٣٤٣٠٥
دبي - أ.ع.م



Al Hadeeqa Contracting Co. L.L.C

شركة الحديقة للمقاولات ش.ذ.م.م

CONTACT, NOTES & AUTHORISATION

Al Hadeeqa Contracting Co. L.L.C | Dubai, U.A.E | alhadeeqallc.com

GET IN TOUCH — FREE SITE ASSESSMENT AVAILABLE

Tel: +971 4 263 2371 | Mobile: +971 544419854 / +971 504824621

Email: alhadeeqallc@gmail.com | Web: www.alhadeeqallc.com

P.O. Box 234305, Dubai, U.A.E

PRICING SUMMARY

TIER	TYPE	SIZE	CAPACITY	STARTING FROM (AED)
Emergency Pod	Precast	7–8 sqm	2–4 people	100,000
Compact Shelter	Precast	15–20 sqm	6–8 people	200,000
Shelter	Poured-in-place	28 sqm (7×4m)	8–15 people	500,000
Safe Room	Poured-in-place	50–80 sqm	10–20 people	950,000
Fortified Residence	Poured-in-place	100–150 sqm	15–25 people	1,900,000
The Vault	Poured-in-place	300–500+ sqm	Custom	5,000,000+
Custom (any tier)	Poured-in-place	Any size	As required	15,200/sqm

GENERAL NOTES

- All prices are indicative starting prices. Final price depends on site conditions, location and specification.
- Precast units (Pod, Compact) manufactured at Al Hadeeqa's Ajman yard and delivered by truck.
- Shelter tier and above are built on-site using traditional formwork at AED 15,200/sqm for custom sizes.
- Delivery, crane hire and installation are charged separately unless stated otherwise.
- A free site assessment is offered to all enquiries — this confirms feasibility and exact pricing.
- Developer / municipality NOC and approval fees are excluded from all prices.
- VAT at 5% is charged on all invoices. All structural designs confirmed by a UAE-licensed engineer.
- Al Hadeeqa holds ISO 9001:2015, ISO 14001:2015 and OHSAS 18001:2007 certifications.
- The Vault is a separate product. Contact Al Hadeeqa for The Vault concept brief.

Authorised Signature
Al Hadeeqa Contracting Co. L.L.C



CERTIFICATIONS



Tel.: +971 4 263 2371
Fax: +971 4 263 3276
P.O.Box: 234305
Dubai - U.A.E

Mobile: +971 544419854
+971 504824621
E-mail: alhadeeqallc@gmail.com

تليفون : +971 4 263 2371
ت / فاكس : +971 4 263 3276
ص.ب : ٢٣٤٣٠٥
دبي - أ.ع.م